

Vidyasagar Central Co-operative  
Bank Ltd., Midnapore  
Head office: - Midnapore  
At & P.O. - Midnapore



Telephone - 03222-275417, 275411  
FAX - 03222 - 275411  
E-mail - vccbmidnapore@gmail.com  
Dist. - Paschim Medinipur

**Memo- Dev /14**

**Date- 29/04/2022**

## **Notice Inviting Quotation**

**Notice inviting quotations for construction of Office Room (CIVIL WORKS) at 2<sup>nd</sup> Floor of Head Office Vidyasagar CCB Ltd., at Midnapore, PO: Midnapore, Dist.:- Paschim Medinipur.**

Sealed item rate quotations are hereby invited from reputed & experienced person /Supplier/Vendor/ Agencies.

**Location/Place: - Vidyasagar Central Co-operative Bank Ltd., Midnapore, Head Office.**

**Completion time:- 60 days from the date of issue of Work Order .**

**Last date & time of submission of Quotation:- 17/05/2022 up to 12 noon**

**Date & time of Opening of Quotation:- 17/05/2022 at 3 pm**

**Description of works :-** Work should be done as per the details and instruction given by Engineer/ authority of the Bank.

**Details of the Work:** The total work has been divided in to Four segments the preferences are mentioned hereunder :

**A) Civil Works consist of Concreting, Brick work, Plastering etc.:** Cement must be of Lafarge-Concreto/ Ultratech-premium/ ACC-F2R. Reinforcement steel must be of Shyam/ TATA/ SAIL/ SRMB/ JINDAL make. 1<sup>st</sup> Class bricks to be provided as well as well graded sand and coarse aggregates to be provided.

**Terms & condition : Supporting documents should be submitted in qualification bid and also will have to be submitted PT, Trade license. Clearance certificate, PAN CARD, GST Registration.**

**1)** All bid must be accompanied by a refundable earnest money / bid security amount to Rs.10000/- as mentioned in the form of Bank Draft / Bankers Cheques in favour of Vidyasagar Central Co- Operative Bank Ltd., Midnapore .

**2)** The quotation should indicate specifically the basic price ,taxes, other duties if any per sq.ft no additional information will be entertained after due date.

**3)**No revision of rates shall be allowed except taxes / charges levied by the Central / State by dully notified only.

Contd. to overleaf.....

- 4)** No advance or running payment shall be made. Payment shall be released after the satisfactory work as mentioned above and providing & fixing of allied works
- 5)** No deviation from the specification shall be allowed without prior consent of authority.
- 6)** All rubbish and superfluous materials shall be removed from site at the cost of contractor after the completion of work and prior to submission of final bill. Rubbish may be disposed outside of premises.
- 7)** The contractor shall make arrangements for storage of material, tools and equipment etc at the site and Bank shall not bear any expenses and risks also on this account.
- 8)** The contractor shall observe all necessary precautions at his cost to safeguard the workers during execution of work.
- 9)** 90% payment against inspection acceptance delivery and completion of works and balance 10% will be paid after 6 months of warranty period. And also that the Payment will be made on successfully completion of work as per work order through account payee cheque or by transfer through NEFT/ RTGS .
- 10)** The undersigned is the accepting authority who reserves the right to reject any or all quotations without assigning any reason and any notice or he will not bound to accept either the lowest tender at any of the bidders.

**For further details please contact P & D Section , H.O. Midnapore or see notice Board of the Bank or visit our Banks website [www.vidyasagarccb.in](http://www.vidyasagarccb.in)**

**Date:- 29/04/2022**

**General Manager**

Vidyasagar Central Co-operative  
Bank Ltd., Midnapore  
Head office: - Midnapore  
At & P.O. - Midnapore



Telephone - 03222-275417, 275411  
FAX - 03222 - 275411  
E-mail - vccbmidnapore@gmail.com  
Dist. - Paschim Medinipur

**Memo- Dev /13**

**Date- 29/04/2022**

## **Notice Inviting Quotation**

**Notice inviting quotations for construction of Office Room (ROOF PROFILE SHED WORKS) at 2<sup>nd</sup> Floor of Head Office Vidyasagar CCB Ltd., at Midnapore, PO: Midnapore, Dist.: -Paschim Medinipur.**

Sealed item rate quotations are hereby invited from reputed & experienced person /Supplier/Vendor/ Agencies.

**Location/Place: - Vidyasagar Central Co-operative Bank Ltd., Midnapore, Head Office.**

**Completion time:- 20 days from the date of issue of Work Order .**

**Last date & time of submission of Quotation:- 17/05/2022 up to 12 noon**

**Date & time of Opening of Quotation:- 17/05/2022 at 3 pm**

**Description of works :-** Work should be done as per the details and instruction given by Engineer/ authority of the Bank.

**Details of the Work:** The total work has been divided in to Four segments the preferences are mentioned hereunder :

**A) Roof Profile Shed and Support Truss : Must be made of TATA brand.**

**Terms & condition : Supporting documents should be submitted in qualification bid and also will have to be submitted PT, Trade license. Clearance certificate, PAN CARD, GST Registration.**

**1)** All bid must be accompanied by a refundable earnest money / bid security amount to Rs.10000/- as mentioned in the form of Bank Draft / Bankers Cheques in favour of Vidyasagar Central Co- Operative Bank Ltd., Midnapore .

**2)** The quotation should indicate specifically the basic price ,taxes, other duties if any per sq.ft no additional information will be entertained after due date.

**3)**No revision of rates shall be allowed except taxes / charges levied by the Central / State by dully notified only.

**4)** No advance or running payment shall be made. Payment shall be released after the satisfactory work as mentioned above and providing & fixing of allied works

Contd. to overleaf.....

- 5) No deviation from the specification shall be allowed without prior consent of authority.
- 6) All rubbish and superfluous materials shall be removed from site at the cost of contractor after the completion of work and prior to submission of final bill. Rubbish may be disposed outside of premises.
- 7) The contractor shall make arrangements for storage of material, tools and equipment etc at the site and Bank shall not bear any expenses and risks also on this account.
- 8) The contractor shall observe all necessary precautions at his cost to safeguard the workers during execution of work.
- 9) 90% payment against inspection acceptance delivery and completion of works and balance 10% will be paid after 6 months of warranty period. And also that the Payment will be made on successfully completion of work as per work order through account payee cheque or by transfer through NEFT/ RTGS .
- 10) The undersigned is the accepting authority who reserves the right to reject any or all quotations without assigning any reason and any notice or he will not bound to accept either the lowest tender at any of the bidders.

**For further details please contact P & D Section , H.O. Midnapore or see notice Board of the Bank or visit our Banks website [www.vidyasagarccb.in](http://www.vidyasagarccb.in)**

**Date:- 29/04/2022**

**General Manager**

---

Vidyasagar Central Co-operative  
Bank Ltd., Midnapore  
Head office: - Midnapore  
At & P.O. - Midnapore



Telephone - 03222-275417, 275411  
FAX - 03222 - 275411  
E-mail - vccbmidnapore@gmail.com  
Dist. - Paschim Medinipur

**Memo- Dev /15**

**Date- 29/04/2022**

## **Notice Inviting Quotation**

**Notice inviting quotations for construction of Office Room (PAINTING WORKS) at 2<sup>nd</sup> Floor of Head Office Vidyasagar CCB Ltd., at Midnapore, PO: Midnapore, Dist.:-Paschim Medinipur.**

Sealed item rate quotations are hereby invited from reputed & experienced person /Supplier/Vendor/ Agencies.

**Location/Place: - Vidyasagar Central Co-operative Bank Ltd., Midnapore, Head Office.**

**Completion time:- 30 days from the date of issue of Work Order .**

**Last date & time of submission of Quotation:- 17/05/2022 up to 12 noon**

**Date & time of Opening of Quotation:- 17/05/2022 at 3 pm**

**Description of works :-** Work should be done as per the details and instruction given by Engineer/ authority of the Bank.

**Details of the Work:** The total work has been divided in to Four segments the preferences are mentioned hereunder :

**A) Painting Work in both inside and outside of the constructed building :** Dulux Weather-shield or equivalent for Outside painting, Asian Paints interior emulsion or equivalent for interior painting.

**Terms & condition :** Supporting documents should be submitted in qualification bid and also will have to be submitted PT, Trade license. Clearance certificate, PAN CARD, GST Registration.

**1)** All bid must be accompanied by a refundable earnest money / bid security amount to Rs.10000/- as mentioned in the form of Bank Draft / Bankers Cheques in favour of Vidyasagar Central Co- Operative Bank Ltd., Midnapore .

**2)** The quotation should indicate specifically the basic price ,taxes, other duties if any per sq.ft no additional information will be entertained after due date.

**3)**No revision of rates shall be allowed except taxes / charges levied by the Central / State by dully notified only.

**4)** No advance or running payment shall be made. Payment shall be released after the satisfactory work as mentioned above and providing & fixing of allied works

Contd. to overleaf.....

- 5)**No deviation from the specification shall be allowed without prior consent of authority.
- 6)**All rubbish and superfluous materials shall be removed from site at the cost of contractor after the completion of work and prior to submission of final bill. Rubbish may be disposed outside of premises.
- 7)** The contractor shall make arrangements for storage of material, tools and equipment etc at the site and Bank shall not bear any expenses and risks also on this account.
- 8)** The contractor shall observe all necessary precautions at his cost to safeguard the workers during execution of work.
- 9)** 90% payment against inspection acceptance delivery and completion of works and balance 10% will be paid after 6 months of warranty period. And also that the Payment will be made on successfully completion of work as per work order through account payee cheque or by transfer through NEFT/ RTGS .
- 10)** The undersigned is the accepting authority who reserves the right to reject any or all quotations without assigning any reason and any notice or he will not bound to accept either the lowest tender at any of the bidders.

**For further details please contact P & D Section , H.O. Midnapore or see notice Board of the Bank or visit our Banks website [www.vidyasagarccb.in](http://www.vidyasagarccb.in)**

**Date:- 29/04/2022**

**General Manager**

Vidyasagar Central Co-operative  
Bank Ltd., Midnapore  
Head office: - Midnapore  
At & P.O. - Midnapore



Telephone - 03222-275417, 275411  
FAX - 03222 - 275411  
E-mail - vccbmidnapore@gmail.com  
Dist. - Paschim Medinipur

**Memo- Dev /16**

**Date- 29/04/2022**

## **Notice Inviting Quotation**

**Notice inviting quotations for construction of Office Room (CARPENTRY WORKS) at 2<sup>nd</sup> Floor of Head Office Vidyasagar CCB Ltd., at Midnapore, PO: Midnapore, Dist.:- Paschim Medinipur.**

Sealed item rate quotations are hereby invited from reputed & experienced person /Supplier/Vendor/ Agencies.

**Location/Place: - Vidyasagar Central Co-operative Bank Ltd., Midnapore, Head Office.**

**Completion time:- 20 days from the date of issue of Work Order .**

**Last date & time of submission of Quotation:- 17/05/2022 up to 12 noon**

**Date & time of Opening of Quotation:- 17/05/2022 at 3 pm**

**Description of works :-** Work should be done as per the details and instruction given by Engineer/ authority of the Bank.

**Details of the Work:** The total work has been divided in to Four segments the preferences are mentioned hereunder :

**A) Carpentry & Furniture Works in terms of Wooden Door with shutter, Aluminum Sliding Window, Floor mat and False ceiling :** Sal wood and century ply for wooden works. Armstrong brand for False Ceiling and PVC Flooring. Anodized double powder coated for Aluminum Window preferably of LYKA brand.

**Terms & condition : Supporting documents should be submitted in qualification bid and also will have to be submitted PT, Trade license. Clearance certificate, PAN CARD, GST Registration.**

**1)** All bid must be accompanied by a refundable earnest money / bid security amount to Rs.10000/- as mentioned in the form of Bank Draft / Bankers Cheques in favour of Vidyasagar Central Co- Operative Bank Ltd., Midnapore .

**2)** The quotation should indicate specifically the basic price ,taxes, other duties if any per sq.ft no additional information will be entertained after due date.

**3)**No revision of rates shall be allowed except taxes / charges levied by the Central / State by dully notified only.

Contd. to overleaf.....

- 4)** No advance or running payment shall be made. Payment shall be released after the satisfactory work as mentioned above and providing & fixing of allied works
- 5)** No deviation from the specification shall be allowed without prior consent of authority.
- 6)** All rubbish and superfluous materials shall be removed from site at the cost of contractor after the completion of work and prior to submission of final bill. Rubbish may be disposed outside of premises.
- 7)** The contractor shall make arrangements for storage of material, tools and equipment etc at the site and Bank shall not bear any expenses and risks also on this account.
- 8)** The contractor shall observe all necessary precautions at his cost to safeguard the workers during execution of work.
- 9)** 90% payment against inspection acceptance delivery and completion of works and balance 10% will be paid after 6 months of warranty period. And also that the Payment will be made on successfully completion of work as per work order through account payee cheque or by transfer through NEFT/ RTGS .
- 10)** The undersigned is the accepting authority who reserves the right to reject any or all quotations without assigning any reason and any notice or he will not bound to accept either the lowest tender at any of the bidders.

**For further details please contact P & D Section , H.O. Midnapore or see notice Board of the Bank or visit our Banks website [www.vidyasagarccb.in](http://www.vidyasagarccb.in)**

**Date:- 29/04/2022**

**General Manager**



# Vidyasagar Central Co-Operative Bank Ltd., Midnapore

## Estimate for CIVIL works

### Head office 2nd Floor Room (West Side)

Sl. No.	Item Description	Quantity	Units	Per unit Rate	TOTAL AMOUNT
1	Dismantling terraced roof in ground floor roof (including floor finish, if any.) taking out carefully tiles with beams, joists, tees or burgahs covering floor below, sorting and stacking sevicable materials at site and removing rubbish as directed within a lead of 75 m. In First Floor Roof ( Item No 4, Page No 8 )	52.05	Sq mt		-
2	Ordinary Cement concrete (mix 1:2:4) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement,if any, in ground floor as per relevant IS codes.	4.035	CUM		-
3	Controlled Cement concrete with well graded stone chips (20 mm graded nominal size) excluding shuttering and reinforcement with complete design of concrete as per IS : 456 and relevant special publications, submission of job mix formula after preliminary mix design after testing of concrete cubes as per direction of Engineer-in charge. Consumption of cement will not be less than 300 Kg of cement with Super plasticiser per cubic meter of controlled concrete but actual consumption will be determined on the basis of preliminary test and job mix fomula. In ground floor and foundation. [using concrete mixture] (a) M 25 Grade	10.3245	CUM		-
4	Reinforcement for reinforced concrete works in all sorts of structures including distribution bars stirrups , binders etc. initial straightening and removal of loose rust (if necessary), cutting to requisite length, hooking and bending to correct shape, placing in proper position and binding with 16 gauge black annealed wire at every intersection, complete as per drawing and direction. For wors in foundation, basement and upto roof of ground floor or upto 4 m Tor steel/ Mild Steel	1.54	MT		-
5	Brick work with 1st class bricks in cement mortar (1:6) (b) In superstructure, ground floor	5.313	CUM		-
5(A)	125mm thick Brick work with First class Bricks in cement mortar (1:4) in Ground Floor	96.76	SQM		-
6	Hire and labour charges for shuttering with centering and necessary staging upto 4 m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams and columns, lintels curved or straight including fitting, fixing and striking out after completion of works (upto roof of ground floor) (When the height of a particular floor is more than 4 m the equivalent floor height shall be taken as 4 m and extra for works beyond the initial 4 m ht. shall be allowed under 12 (e) for every 4 m or part thereof)	109.206	SQM		-
	(a) 25 mm to 30 mm thick wooden shuttering as per decision & direction of Engineer-In-Charge		SQM		-
7	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface]	118.54	SQM		-
	(ii) With 1:4 cement mortar (inside Plaster)	0	SQM		-
	(a) 15 mm thick plaster ( 2nd Floor Extra cost Rs. 4.00 per floor)	0	SQM		-
8	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface]	108.35	SQM		-
	(ii) With 1:6 cement mortar (Outside Plaster)		SQM		-
	(a) 20 mm thick plaster ( 2nd Floor Extra cost Rs. 4.00 per floor)		SQM		-
9	PVC 25-mm	40	MTR		-
10	PVC 15-mm	20	MTR		-
11	M.S or W.T. ornamental grill of approved design joints continuously welded with M.S. or W.I. flats and bars of windows , railing etc.fitted and fixed with necessary screws and lugs in ground floor.grill weighing above 10kg/sqm and upto 16 kg/sqm.	3.56	QNTL		-
<b>Total=</b>				<b>Rs.</b>	<b>-</b>

# Vidyasagar Central Co-Operative Bank Ltd., Midnapore

## Estimate for Painting Work

### Head office 2nd Floor Room (West Side)

Sl. No.	Item Description	Quantity	Units	Per unit Rate	TOTAL AMOUNT
1	Removing loose scales, blisters etc. from old painted surface and thoroughly smoothening the surface to make the same suitable for receiving fresh coat of paint. Page No : 175, Item No : 01	61.6	sqmt		-
2	Applying Interior grade Acrylic Primer of approved quality and brand on plastered or concrete surface old or new surface to receive Distemper/ Acrylic emulsion paint including scraping and preparing the surface thoroughly, complete as per manufacturer's specification and as per direction of the EIC. (In Ground Floor) (a) One Coat i) Water based interior grade Acrylic Primer in First Floor( Item No :14 ; Page No : 171 )	141.6	sqmt		-
3	Applying Acrylic Emulsion Paint of approved make and brand on walls and ceiling including sand papering in intermediate coats including putty (to be done under specific instruction of Superintending Engineer): (Two coats) i) Standard Quality Sq.M ( Item No : 9, Page No :177 )	141.6	sqmt		-
4	(b) Rendering the surface of walls and ceiling with white cement based wall putty of approved make and brand(1.5mm thick) Wherever required on rough surface ( Item No: 5(b) , Page No: 175 )	141.6	sqmt		-
5	(A) Painting with best quality synthetic enamel paint of approved make and brand including smoothening surface by sand papering etc.including using of approved putty etc. on the surface, if necessary : (b) On steel or other metal surface : (iv) Two coats (with any shade except white)	32.15	sqmt		-
6	Removing old scales, blisters etc. of interior surface of walls, ceiling by scraping etc. and preparing smooth and even surface with rendering or cement mortar (1:2) (as necessary), to make the surface suitable for receiving distemper. (Payment against this item will be made only when this has been done on the specific direction of the Engineer-in-charge	58.74	sqmt		-
7	Applying exterior grade Acrylic Primer of approved quality and brand on plastered or concrete surface old or new surface to receive Distemper/ Acrylic emulsion paint including scraping and preparing the surface thoroughly, complete as per manufacturer's specification and as per direction of the EIC. (In Ground Floor) (a) One Coat i) Water based interior grade Acrylic Primer in First Floor( Item No :14 ; Page No : 171 )	128.74	sqmt		-
8	Applying Acrylic Emulsion Paint (Weather coat) of approved make and brand on walls and ceiling including sand papering in intermediate coats including putty (to be done under specific instruction of Superintending Engineer): (Two coats) i) Standard Quality Sq.M ( Item No : 9, Page No :177 )	128.74	sqmt		-
<b>Total=</b>				Rs.	-

Inside Painting

Outside Painting

## Vidyasagar Central Co-Operative Bank Ltd., Midnapore

Providing & fixing of GI Sheet & Supporting Trusses (at 2nd Floor) At Chotobazar, Post: Midnapore , Dist.:-Paschim Medinipur

### Estimate for Profile Shed Work

#### Head office 2nd Floor Room (West Side)

SL. NO	DESCRIPTION OF WORK	Nos	QTY.	UNIT	RATE RS.	AMOUNT RS.
1	Galvanised plain sheet works (excluding supporting framework) fitted and fixed with 6 mm. dia J or L hook-bolts and nuts, sheet-bolts, limpet and bitumen washers and putty with 150 mm. end lap & 50 mm minimum side lap complete.	1	100.85	sqmt		0.00
	In 2nd Floor Roof: with 0.63 mm. sheets.	1		sqmt		
	<b>( Item No 28, Page No 66 )</b>	1		sqmt		
2	M.S. structural works in columns, beams etc. with simple rolled structural members (e.g. joists, angle, channel sections conforming to IS: 226, IS: 808 & SP (6)- 1964 connected to one another with bracket, gussets, cleats as per design, direction of Engineer-in-charge complete including cutting to requisite shape and length, fabrication with necessary bolting, metal arc welding conforming to IS: 816- 1956 & IS: 1995 using electrodes of approved make and brand conforming to IS:814- 1957, haulage, hoisting and erection all complete. (The rate includes the cost of rolled steel section, consumables such as electrodes, gas and hire charge of all tools and plants and labour required for the work including all incidental chages such as electricity charges, labour insurance charges etc. Payment to be made on the basis of calculated weight of structural members only in finished work as per IS specified weight. Payment for gusset, bracket, cleat, rivets, bolts and nuts may be make by adding the actual weight of such items with the weight of finished structural members or 7% of weight for finished structural members weighing not less than 22.5 Kg. / m. or 15 % of weight for finished structal members weighing less than 22.5 Kg. / m. may be increased allow for bracket, cleat, rivet, bolts and nuts etc. and no seperate payment being made for these items, as per direction of Engineer In Charge. The rates are considered for a height of erection 8m. / 2nd floor level from the ground. Add 1.5% extra over the rate for each additional floor or 4m. beyond initiaal 8m. or part thereof.)	1	1.36	MT		0.00
	I) For structural members of specified sections weighing less than 22.5 Kg./m	1		sqmt		
	<b>( Item No 01, Page No 74 )</b>	1		sqmt		0.00
					Total	= 0.00
					Cost for Civil works	= 0.00
					Cost for Painting works	= 0.00
					Cost for Carpentry works	= 0.00
					<b>Total cost for construction</b>	<b>= 0.00</b>

# Vidyasagar Central Co-Operative Bank Ltd., Midnapore

## Estimate for Carpentry Works

### Head office 2nd Floor Room (West Side)

Sl. No.	Item Description	Quantity	Units	Per unit Rate	TOTAL AMOUNT
1	<p>Providing and fixing of false ceiling with powder coated exposed G.I. grid suspension system (E-Grid U-1520 or equivalent load carrying capacity with mid span deflection not exceeding 1/360 span with hanger spacing of 1200mm c/c ) consisting of Main Runner 3600 mm long, Cross Tee 1200 mm / 600 mm long and Wall Angle. The Wall Angle shall be fixed on PVC Dash Fasteners on the perimeter of the wall by steel screws with distance 300mm c/c. The Main Runners to be placed @ 1200 mm. The Cross Tee 1200mm will be inserted in the pre-cut slots of Main Runner at a regular interval of 600 mm to form a modular grid of 1200mm X 600mm. Additional Cross Tees of 600 mm shall be placed perpendicular to the Cross Tee 1200 mm long to finally form a grid of 600 mm X 600 mm. Grid of module size 600 mm X 600 mm shall be supported by 6 mm dia G.I. wire from purlins / soffit. 15mm thick OW Acoustic Board (Mineral Fiber Acoustic Ceiling Tiles) of approved pattern and size 595mm X 595mm with NRC value &gt; 0.65 should be placed in the Grid module to form a False Ceiling. All complete as per the drawing &amp; directions of Engineer-in-charge.</p> <p style="margin-left: 40px;">a) Acoustic False Ceiling (with 15mm thick OW Acoustic Board and E-Grid U-1520). of Armstrong Make</p>	945.00	Sq Ft		-
2	Suppling for Flush door shutter 37mm thk over laminate sheet of approved shade both faces of the fitting steel hinges, with handle of approved make and quality.	25.00	Sq Ft		-
3	Wood Work in Door & window Frame Filled & Fixed Complete Including Protective Coat.	0.078	Cum		-
4	<p>Supplying profiles of required section made of Aluminium Alloy Extrusions conforming to IS: 732-1983 and IS: 1285- 1975; Annodized (with required film thickness and specified colour / natural) matt finished conforming to IS: 1868-1983 for fabrication of composit door, sliding &amp; casement windows, partitions, formed of basic sections of any ISI embossed / certified make and brand as per direction of Engineer - In-Charge. (Payment will be made on finished length of the work).</p> <p style="margin-left: 40px;">(A) In 10-12 Micron thickness Annodizing film</p> <p style="margin-left: 80px;">I) Natural white</p> <p style="margin-left: 40px;">a) 2- track sliding window</p> <p style="margin-left: 40px;">i) Bottom frame, Top and side Frame</p> <p style="margin-left: 40px;">( Item No: 1 , Page No: 206 )</p>	176	Sqft		-
5	Supplying for Armstrong PVC Floor made of 2 mm thk pvc floor layng for serfacing compound filler and leabeling and Adhesive pesting.	945.00	Sqft		-
<b>Total=</b>				<b>Rs.</b>	<b>-</b>