Vidyasagar Central Co-operative Bank Ltd., Midnapore Head office: - Midnapore At & P.O. - Midnapore



Telephone - 03222-275417, 275411

FAX - 03222 - 275411

E-mail - vccbmidnapore@gmail.com

Dist. - Paschim Medinipur

Memo-Dev /258

Date- 26/10/2022

Notice Inviting Quotation

Notice inviting quotations for construction of Toilet (West side) at 2nd Floor of Head Office Vidyasagar CCB Ltd., at Midnapore, PO: Midnapore, Dist.:-Paschim Medinipur.

Sealed item rate quotations are hereby invited from reputed & experienced person /Supplier/Vendor/ Agencies.

Location/Place: - Vidyasagar Central Co-operative Bank Ltd., Midnapore, Head Office.

Completion time: - 60 days from the date of issue of Work Order .

Last date & time of submission of Quotation:- 07/11/2022 up to 12 noon

Date & time of Opening of Quotation:-

07/11/2022 at 3 pm

Description of works :- Work should be done as per the details and instruction given by Engineer/ authority of the Bank.

Details of the Work: The total work has been divided in to Four segments the preferences are mentioned hereunder:

A) Civil Works consist of Plastering, Tile Flooring, UPVC fittings, Plumbing fittings etc.: Cement must be of Lafarge-Concreto/ Ultratech-premium/ ACC-F2R. 1st Class bricks as well as well graded sand to be provided. Jhonson / Kajaria/ or any other approved brand of tiles to be used. Jaquar & ESSCO brand of plumbing fittings are to be used.

Terms & condition: Supporting documents should be submitted in qualification bid and also will have to be submitted PT, Trade license. Clearance certificate, PAN CARD, GST Registration.

- 1) All bid must be accompanied by a refundable earnest money / bid security amount to Rs.1000/-as mentioned in the form of Bank Draft / Bankers Cheques in favour of Vidyasagar Central Co-Operative Bank Ltd., Midnapore.
- 2) The quotation should indicate specifically the basic price ,taxes, other duties if any per sq. ft no additional information will be entertained after due date.
- **3)**No revision of rates shall be allowed except taxes / charges levied by the Central / State by dully notified only.

Contd. to overleaf....

- **4)** No advance or running payment shall be made. Payment shall be released after the satisfactory work as mentioned above and providing & fixing of allied works
- 5)No deviation from the specification shall be allowed without prior consent of authority.
- **6)**All rubbish and superfluous materials shall be removed from site at the cost of contractor after the completion of work and prior to submission of final bill. Rubbish may be disposed outside of premises.
- 7) The contractor shall make arrangements for storage of material, tools and equipment etc at the site and Bank shall not bear any expenses and risks also on this account.
- 8) The contractor shall observe all necessary precautions at his cost to safeguard the workers during execution of work.
- **9)** 90% payment against inspection acceptance delivery and completion of works and balance 10% will be paid after 6 months of warranty period. And also that the Payment will be made on successfully completion of work as per work order through account payee cheque or by transfer through NEFT/ RTGS .
- 10) The undersigned is the accepting authority who reserves the right to reject any or all quotations without assigning any reason and any notice or he will not bound to accept either the lowest tender at any of the bidders.

For further details please contact P & D Section , H.O. , Midnapore or see notice Board of the Bank or visit our Banks website www.vidyasagarccb.in

Date:- 29/10/2022

General Manager

sed estimate for construction of Staff Toilet at newly constructed Office (West Side) of H.O. at 2nd Floor of Head Office at- Chotobazar , PO: Midnapore, Dist: Paschim Medinipur

	Rates are as per PWD 2017 schedule				
2	Description	Qnty.	Rate	Unit	Amount
1	Ordinary Cement concrete (mix 1:1.5:3) with graded stone chlps (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes. (i) Pakur Variety	1.000		Cum	0.00
2	Supplying, fitting and fixing Marble Slab/tile of 15 to 18 mm thickness in floor, lobby, stair, landing & treads etc. over 20 mm (av.) thck base of Cement mortar (1:2) laid with white cement slurry @ 4.4 kg/Sq.m before placing marble & jointed with white cement slurry @ 2.0 kg/Sq.m with necessary pigments including grinding and Granite polishing as per direction of Engineering -in -Charge in Ground Floor. {White cement and Pigment to be supplied by the Agency] Area of each Slab/tile exceeding 0.60 sq.m but not exceeding 1.00 sq.m.	8.050		Sqm	0.00
3	Supplying, fitting & fixing 1st quality Ceramic tiles in walls and floors to match with the existing work & 4 nos. of key stones (10mm) fixed with araldite at the back of each tile & finishing the joints with white cement mixed with colouring oxide if required to match the colour of tiles including roughening of concrete surface, if necessary or by synthetic adhesive & grout materials etc. (A) Floor With Sand Cement Mortar (1:4) 20 mm thick & 2 mm thick cement slurry at back side of tiles using cement @ 2.91 Kg/Sq.m & joint filling using white cement slurry @ 0.20kg/Sq.m. Area of each tile above 0.09 Sq.m (i) Coloured decorative	21.000		Sqm	0.00
4	Supplying, fitting and fixing PVC pipes of approved make of Schedule 80 (medium duty) conforming to ASTMD - 1785 and threaded to match with GI Pipes as per IS: 1239 (Part - I). with all necessary accessories, specials viz. socket, bend, tee, union, cross, elbo, nipple, longscrew, reducing socket, reducing tee, short piece etc. fitted with holder bats clamps, including cutting pipes, making threads, fitting, fixing etc. complete in all respect including cost of all necessary fittings as required, jointing materials and two coats of painting with approved paint in any position above ground. (Payment will be made on the centre line measurements of total pipe line including all specials. No separate payment will be made for accessories, specials. Payment for painting will be made seperately) (a) For Exposed Work PVC Pipes				
	125mm	13.000		Mtr.	0.00
	20mm dia	12.000		Mtr.	0.00
	25mm dla	8.000		Mtr.	0.00
5	Supplying, fitting and fixing Flat back urinal (half stall urinal) in white vitreous chinaware of approved make in position with brass screws on 75 mm X 75 mm X 75 mm wooden blocks complete. (I) 635 mm X 395 mm X 420 mm	1.000		Each	0.00
6	Supplying, fitting and fixing urinal flush pipe fittings of approved brand. C.P. urinal flush pipe fittings range of two	1.000		Each	0.00
7	Supplying, fitting and fixing Squating plate with integral flushing in white vitreous chinaware of approved make in cement concrete (6:3:1) with jhama chips complete. (Payment of concrete will be paid seperately). (I) 450 mm X 350 mm	1.000		Each	0.00
8	Supplying, fitting and fixing shower of approved brand and make. Hand Shower(Health Faucet) with 1mtr Fexible Tube with Wall Hook(Equivalent to Code No.573 & Model -ALLIED of Jaquar or similar).	2.000		Each	0.00
9	Supplying, fitting and fixing bib cock or stop cock. Chromium plated Concealed Stop Cock (Equivalent to Code No. 514(A) & Model - Tropical / Sumthing Special of ESSCO or similar brand).	4.000		Each	0.00
10	Supplying, fitting and fixing pillar cock of approved make. CP Pillar Cock - 15 mm. (Equivalent to Code No. 507 & Model - Tropical / Sumthing Special of ESSCO or similar brand).	1.000		Each	0.00
11	Supplying, fitting and fixing approved brand 32 mm dia.P.V.C. waste pipe, with PVC coupling at one end fitted with necessary clamps. 600 mm long	4.000		Each	0.00
12	Supplying, fitting and fixing approved brand P.V.C. CONNECTOR white flexible, with both ends coupling with heavy brass C.P. nut, 15 mm dia. (i) 300 mm long	4.000		Each	0.00
13	Wash basin vitreous china of approved make (without fittings) supplied,fitted and fixed in position on 75mm X 75 mm X 75 mm wood blocks and C.I. brackets including two coats of painting of C.I. brackets. 630 mm X 450 mm size	1.000		Each	0.00
14	Supplying, fitting and fixing bevelled edged mirror 5.5 mm thick silver red as per I.S. 3438 / 1965 together with brass C.P. hinges. (i) 450 mm X 300 mm	1.000		Each	0.00
15	Supplying, fitting and fixing soap holder. (a) PTMT (Prayag or equivalent)	1.000		Each	0.00
16	Supplying, fitting and fixing towel rall with two brackets.	1.000		Each	0.00
	25 mm dia. and 750 mm long	1		Total =	0.00
	Add CGST @ 9%	r		iotai =	0.00
					0.00
	Add CGST @ 9% Add SGST @ 9%				0.00